LITZKEE
Poultry Heating Systems

# 900KW WATER KETTLE/BOILER – SPECIFICATIONS

| GENERAL DETAILS | |
|---|---|
| **DESCRIPTION** | **900KW** |
| EXTERNAL SIZE | 1,8M X 3,3M X 2M H |
| WEIGHT (ESTIMATE) | 6000KG |
| SLAB SIZE REQUIRED | 6M X 6M X 200MM |
| **MATERIAL** | |
| BASE | 406 IBEAM(39KG/PM) |
| CHIMNEY | S/STEEL |
| CHIMNEY BOX | 5MM |
| CLADDING | S/STEEL |
| DOME | 6MM |
| HOPPER | S/STEEL |
| **ELECTRONICS** | |
| CONTROL BOX (S/STEEL) | YES |
| DIRECT DRIVE GEARBOX & MOTOR | YES |
| DOUBLE PUMP SYSTEMS | 2,2KW |
| ELECTRICITY REQUIRED | 3 PHASE |
| KVA USAGE PER MACHINE (ESTIMATE) | 8KVA |
| STOKER FAN MOTOR | 2,2KW |
| ZEST ELECTRONIC PARTS | YES |

## PAYMENT REQUIREMENTS

- 60% DEPOSIT WITH ACCEPTANCE OF QUOTATION.
- 20% OUTSTANDING WITH FIRST DELIVERY
- 20% OUTSTANDING WITH COMPLETION OF ORDER

## GENERAL INFORMATION & REQUIREMENTS

- MANUFACTURING ACCORDING TO SPECIFICATION LIST PROVIDED.
- CUSTOMER RESPONSIBLE FOR THE CONCRETE SLAB AND SUPPLY OF ELECTRICITY

*900KW = 120 000 CHICKS (ESTIMATE)*
*CHICKENS X 7.5 / 1000 = KW REQUIRED*

**www.litzkee.co.za**